

# 2018 DOE Accelerator Safety Workshop

SLAC, 21 – 23 August 2018

*ESRF upgrade*

*Paul Berkvens*




| The European Synchrotron



## Contents

1. Short introduction to the ESRF
2. EBS project
3. Decommissioning of existing storage ring
4. EBS project: safety management



# ESRF: SHORT INTRODUCTION

## European Synchrotron Radiation Facility


3<sup>rd</sup> generation high energy synchrotron radiation facility

A research facility unique worldwide

- ✓ **6,500 scientific visitors** every year including **4,000 users**
- ✓ **2,000 proposals** per year: **900 accepted**, 1,550 experimental sessions
- ✓ **30% of the research involves industrial developments**

Scientific excellence recognised worldwide


- ✓ N° 1 in scientific output
- ✓ N° 2 in number of users
- ✓ N° 1 in reliability & quality
- ✓ 4 Nobel prize-winners among the ESRF users
- ✓ 25,166 reference articles during the period 1994-2014
- ✓ ~ 30 articles in *Nature* and *Science* per year
- ✓ Nearly 2,000 publications per year: ~ 5 every day



6 GeV storage ring  
31 public beamlines  
12 CRG beamlines




# ESRF UPGRADE: EXTREMELY BRILLIANT SOURCE PROJECT



Parameter	Existing Lattice	New Lattice
Energy, $E$ [GeV]	6.04	6.04
Circumference, $C$ [m]	844	844
RF frequency, $f_{RF}$ [MHz]	352	352
Beam current [mA]	200	200
Horizontal Emittance [ $\text{pm} \cdot \text{rad}$ ]	<b>4000</b>	<b>150</b>
Vertical Emittance [ $\text{pm} \cdot \text{rad}$ ]	4	3
Beta at ID center, $\beta_x$ , $\beta_y$ [m]	37.6, 3.0 (high $\beta$ ) 0.35, 3.0 (low $\beta$ )	3.6, 3.6
Beam size at ID center, $\sigma_x$ , $\sigma_y$ [ $\mu\text{m}$ ]	413, 3.9 (high $\beta$ ) 50, 3.9 (low $\beta$ )	24, 3.3
Beam div. at ID center, $\sigma_x'$ , $\sigma_y'$ [ $\mu\text{rad}$ ]	10, 1.3 (high $\beta$ ) 107, 1.3 (low $\beta$ )	6.4, 0.91

# ESRF UPGRADE: EXTREMELY BRILLIANT SOURCE PROJECT

<b>20 October</b>	<b>2017</b>	<b>Start girder assembly (12 months)</b>
10 December	2018	Start long shutdown (20 Months)
		<b>Dismantling (3 months) and Installation (9 months)</b>
<b>19 November</b>	<b>2019</b>	<b>Start accelerator commissioning</b>
<b>04 March</b>	<b>2020</b>	<b>Start beamlines commissioning</b>
<b>25 August</b>	<b>2020</b>	<b>Back to USM</b>



now

# DECOMMISSIONING OF THE EXISTING STORAGE RING

Revised technical study sent to French Nuclear Safety Authority (ASN) in April 2016:

- Proposed criteria for radiological classification of accelerator components, based on surface dose rate measurements;
- IRSN: technical expertise completed end February 2018 → positive evaluation;
- **Formal approval from ASN in July 2018.**

Radioactive waste management plan submitted to ASN in December 2017:

- Proposed radioactive zoning: part of the injection cell plus the scrapers;
- No radioactive waste: all elements inside radioactive zoning are considered as spare parts.

Radiological hazard analysis of works during long shutdown submitted to ASN in December 2017:

- Assessment of anticipated exposures for activities during the long shutdown, including civil engineering works.

## Radiological hazard analysis for works during long shutdown

### Assessment of anticipated exposures



- Based on measured dose rates inside the tunnel (injection zone, scrapers and straight sections);
- Based on detailed planning of different tasks during dismantling;
- Conservative assumptions concerning time at contact with activated pieces.

Anticipated collective effective dose: 160  $\mu\text{Sv}$  (4 months, 160 people).

Anticipated individual effective doses: < 1  $\mu\text{Sv}$  – 13  $\mu\text{Sv}$ .

During civil works (generation of concrete dust): committed effective dose (50 years) :  $8 \times 10^{-4}$   $\mu\text{Sv}$ .

# DECOMMISSIONING OF THE EXISTING STORAGE RING




- cable trays, cables, piping, screws and bolts, small items
- supports
- front end components
- quadrupoles
- sextupoles
- dipoles
- vacuum vessels

	2019												2020												2021												2022												2023												2024																
	D	J	F	M	A	M	J	J	A	S	O	N	D	D	J	F	M	A	M	J	J	A	S	O	N	D	D	J	F	M	A	M	J	J	A	S	O	N	D	D	J	F	M	A	M	J	J	A	S	O	N	D	D	J	F	M	A	M	J	J	A	S	O	N	D	D	J	F	M	A	M	J	J	A	S	O	N
cable trays, cables, piping, screws and bolts, small items	█																																																																												
supports	█																																																																												
front end components																									█																																																				
quadrupoles																									█												█																																								
sextupoles																																					█												█																												
dipoles																																																	█												█																
vacuum vessels																																																													█																




# DISASSEMBLY OF STORAGE RING COMPONENTS IN ESRF-12

Example: dipole girder G15/G25



# DISASSEMBLY OF G10 GIRDER ON 27 APRIL 2018



## Purpose of the radiation safety assessment

- Show that with the beam loss collimator scheme we can maintain ESRF's radiation protection policy:

$$\int_{4 \text{ hours}} \frac{dE}{dt} \cdot dt < 0.5 \mu\text{Sv/h} \times 4 \text{ h} = 2 \mu\text{Sv}$$

- Evaluate anticipated and public exposure in normal operation.
- Evaluate potential exposures from accidental situations.
- Evaluate activation issues around collimators.
- Injection with front ends open.
- Define required interlocked radiation monitors systems.

## EBS storage ring radiation safety assessment


*SG/RF/Doc/2017-1en, version 29/08/2017*

1. Introduction
2. Radiation protection objectives
3. Methodology
4. Beam loss collimation
5. Normal beam losses
6. Abnormal beam losses
7. Labyrinths and penetrations
8. Vacuum related issues
9. Injection with front ends open
10. Activation issues
11. Anticipated occupational and public exposures in normal operation
12. Interlocked radiation monitors


**Compliance with  
2013/59/EURATOM Directive**

# EBS STORAGE RING RADIATION SAFETY ASSESSMENT

FLUKA model of new storage ring




Model of standard cell of storage ring



FLUKA model of optics hutch

# NORMAL BEAM LOSSES: BEAM LOSS COLLIMATOR – LOCAL SHIELDING



# ANTICIPATED OCCUPATIONAL EXPOSURES

Support groups

Survey and alignment group

	experiments / control hutches		optics hutch		technical zone		tunnel roof		tunnel	
	$\mu\text{Sv/y}$	%	$\mu\text{Sv/y}$	%	$\mu\text{Sv/y}$	%	$\mu\text{Sv/y}$	%	$\mu\text{Sv/h}$	days/y
<b>50/24</b>										
<b>usm</b>	18.69	5			13.84	0	30.94	2		
<b>mdt</b>	4.04	95	10.18	5	9.50	0				
<b>shutdown</b>									0.05	50
<b>total</b>		4.78		0.51		0		0.62		20
<b>85/72</b>										
<b>usm</b>	16.67	5			11.66	0	24.06	2		
<b>mdt</b>	4.38	95	13.91	5	12.84	0				
<b>shutdown</b>									0.05	50
<b>total</b>		4.99		0.70		0		0.48		20

**30.90  $\mu\text{Sv/y}$**


(3 mrem/y)

**31.17  $\mu\text{Sv/y}$**


(3.1 mrem/y)

# ANTICIPATED PUBLIC EXPOSURES

## Gas bremsstrahlung: direct radiation



total effective dose rate ( $\mu\text{Sv/h}$ )



$x = 5500 \text{ cm}$ :


$8.2 \cdot 10^{-5} \mu\text{Sv/h}$  at 200 mA

→ **0.34  $\mu\text{Sv}$**  (24/7 occupancy)

Anticipated public exposure at reference point:  
 $1.8 + 1 + 0.34 = \mathbf{3.14 \mu\text{Sv}}$  (24/7 occupancy)

$$E(x) = 186.3 \frac{1}{x^{1.7}} \mu\text{Sv/h}$$

# INTERLOCKED RADIATION MONITORS



**4 neutron monitors / unit cell:**

$z = -420 \text{ cm}$

$z = 50 \text{ cm}$

$z = 1050 \text{ cm}$

$z = 1460 \text{ cm}$

**Beam loss scenarios:  
faulty steerers**



## EBS radiation shielding review 27-28 June 2017

### Meeting charge

The Committee is asked to critically review the radiation protection safety assessment and, in particular, to advise the ESRF on the following points:

- ALARA: is the optimisation process correctly carried out?
- Are the proposed operational limits and conditions of operation adequate?
- Are all radiation protection issues related to the operation of the new storage ring correctly covered in the safety assessment?
- Is the methodology used for the shielding study appropriate?
- Do the different beam loss scenarios included in the shielding study correctly cover all sources of anticipated and potential exposures, directly related to the operation of the new storage ring?
- Are the values for the anticipated occupational and public exposures realistic?
- Is the proposed interlocked radiation monitoring system adequate and will the system ensure the derived dose limits defined by ESRF?



### **Sayed Rokni** (Chair)

Radiation Protection Department Head  
SLAC National Accelerator Laboratory

### **Yoshihiro Asano**

NewSUBARU  
Former director of safety design group SPring8/RIKEN

### **Doris Forkel-Wirth**

Radiation Protection Group Head  
CERN

### **Stefan Roesler**

Operational Radiation Protection Head  
CERN

## Executive summary

....

This report is the result of the Committee members' review of the large set of very well-prepared documents, and critical review of materials presented during the meeting and discussion with EBS project staff and deliberation among the Committee members.

Based on this review, the Committee believes that EBS project has positively responded to each of the questions in the Charge letter.

...

The beam tracking studies coupled with the detailed FLUKA simulations that are presented in the radiation safety assessment set a high standard for radiation assessment for synchrotron radiation facilities that is commendable.

Throughout the report, a number of Recommendations have been listed. Completion of the Recommendations will ensure a safe and compliant commissioning and operation of the EBS.

## Accelerator + Beamlines Personnel Safety Systems

- Use existing systems, with a number of modifications
- Technical design report sent to ASN, July 2018
- Formal review by the ASN (IRSN) in 2018 / 2019

Les systèmes de sécurité du personnel des accélérateurs et des lignes de lumière de l'ESRF

SG-RP/Doc/PSS/2018-1fr, version 30/06/2018

### Table des matières

1	Introduction	2
2	Généralités	2
2.1	Architecture générale	3
3	Le système de sécurité des accélérateurs	4
3.1	Introduction	4
3.2	Les accès aux tunnels des accélérateurs	5
3.2.1	Les différentes zones	5
3.2.2	Les rondes	6
3.2.3	Accès contrôlé	6
3.2.4	Les schémas logiques pour les différentes zones	7
3.3	Les permis	15
3.3.1	Général	15
3.3.2	Linac	15
3.3.3	Booster	17
3.3.4	Anneau de stockage	20
3.4	Procédure de test pour le PSS des accélérateurs	26
4	Les systèmes de sécurité des lignes de lumière	26
4.1	Introduction	26
4.2	La ronde	27
4.3	Les permis d'ouverture des obturateurs	28
4.4	La cabine optique	28
4.5	Les cabines expérimentales	29
4.6	Les clés de sécurité	30
4.7	Accès d'urgence dans une cabine	30
4.8	Procédure de test pour les PSS des lignes de lumière	30
5	Résumé des modifications au niveau des systèmes de sécurité existants	30









Figure 8 – Schéma logique pour les zones SR3 et SR3a.


# COLLIMATOR CELL: TRANSIENT ACTIVATION AFTER 200 mA BEAM DUMP



# COLLIMATOR CELL: TRANSIENT ACTIVATION AFTER 200 mA BEAM DUMP



# SHUTDOWN PLANNING: STORAGE RING REMOVAL AND INSTALLATION



Internal accelerator Safety & Security review

## Project management for removal and installation activities:

- Project management by Accelerator Project Office (APO)
  - Pantaleo Raimondi (project leader)
  - Paul Berkvens (safety engineer)
  - Due to very tight planning:
    - All tasks must be prepared in great detail
    - Prevention plans with detailed “modes opératoires”
  - During shutdown, daily meetings of APO, coordinators and supervisors
    - PB present or acting safety engineer (Safety Group Unit leaders)
  - During all shifts: presence of (acting) safety engineer
    - Isolated safety issues should be reported by supervisors to (acting) safety engineer
    - More general safety issues will be dealt with during daily coordination meetings

# MANY THANKS FOR YOUR ATTENTION

